

19-3-4 FWA Firewood Laydown Yard

Addendum

October 30, 2020



SALCHA-DELTA SOIL AND WATER CONSERVATION DISTRICT

P.O. Box 547
DELTA JUNCTION, AK 99737
(907) 895-6279
FAX: (907) 895-6278

19-3-4 FWA Firewood Laydown Yard
Addendum

1).

Question:

- Please verify that the aggregate material for this project will be coming from the material site on Sonja Road.

Answer:

- Section 301-2.01 Materials. Use aggregate conforming to Subsection 703-2.09, Table 703-9 Grading A. from the designated SDSWCD material stockpile on Sonja Drive. The material from this source meets the gradation requirements for this project.

2).

Question:

- Please verify that there will be no royalty for the material obtained from the material site on Sonja Road.

Answer:

- The stockpiled material on Sonja Drive is the property of the SDSWCD and has been designated for the construction of the Firewood Yard.

3).

Question:

- Please verify that the material from the Sonja Road is not required to be processed prior to placement on the project.

Answer:

- The material in the stockpile on Sonja Drive meets the requirements for the aggregate for this project. The contractor will be responsible, within reason, to not include any muck, roots, sod, and debris that may be encountered in the stockpile.

4).

Question:

- Is the contractor or the owner responsible for the survey on this project?

Answer:

- Section 105-1.08 Survey Control the SDSWCD will provide sufficient horizontal and vertical control data to establish the planned lines, grades, shapes, and structures. The Contractor shall provide all additional survey work to maintain control during the project.

5).

Question:

- Are there any spring weight restrictions on the haul route to the material source?

Answer:

- Section 107-1.01 Laws to be Observed. The Contractor shall keep fully informed of, observe, and comply with all federal, state, and local laws, ordinances, and regulations, and all orders and decrees of bodies or tribunals having any jurisdiction or authority, that in any manner affect those engaged or employed on the work or which in any way affect the conduct of the work.

19-3-4 FWA Firewood Laydown Yard
Addendum

6).

Question:

- Are there any bridge weight restrictions for the new River Rd bridge over the Chena River on post?

Answer:

- The bridge is posted with a Military Load Classification (MLC) of 70 which is approximately 60 tons.

7).

Question:

- Will a DEC storm water permit and SWPPP be required since the project will disturb over 1 acre?

Answer:

- The area is approximated as a curtesy to aid with estimation of materials.

8).

Question:

- Is a water source available on post for this project?

Answer:

- Water can be obtained from the water point at building 3004 on FWA.

9).

Question:

- Are there any compaction requirements for the subgrade before the geotextile is placed?

Answer:

- Uniform overlapping wheel/track rolling prior to the installation of the geotextile is acceptable means of compaction for the subgrade.

10).

Question:

- At what depth is the aggregate Base required over the geotextile?

Answer:

- Minimum of 12" of aggregate base is required over the geotextile.

11).

Question:

- Is the aggregate base required a C or D1?

Answer:

- Pit run from the designated material source on Sonja Drive is the only aggregate required for this project.